







REVESBY, NSW, AUSTRALIA

OVERVIEW

- 1. Introduction
 - 2. Design
- 3. Installation
- 4. Operation / Climbing Process
 - 5. Compliance
 - 6. Safety and Maintenance
 - 7. Documentation


1. INTRODUCTION


Provides all around safety and edge protection. **Speeds up the construction time in an economical way.** Light weight. Rigid in design. ♦ Minimal vertical gaps (25 mm) opening) Designed to suit any build Quick assembly and erection Fully encapsulated system to prevent fall of personnel and materials Casting Bolts reusable (No need to grind the bolts). After initial training, the system can be operated b

2. DESIGN

- **♦ COVERAGE HEIGHT 7m to 20m.**
 - (Can be used for both structural work and finishing work)
- **♦ WALKWAY PLATFORM Varies from (650mm) to (1000mm)**
- **CLIMBING MECHANISM Crane Assisted or Hydraulic Self-Climbing.**
- ♦ FORMWORK HOIST & ALIMAK Fabquip Hoist and Alimak can be incorporated into the system.
- **TRAILING SCREENS Screens underneath the loading platforms can be** provided.

LAYOUT






SECTION

LOADINGS:

MAXM WIND SPEED DURING LIFTING= 45 km/hr
MAX. LOAD ON EACH NEEDLE = 8 KN
MAX. REACTION LOAD ON SLAB = 16 KN



3. INSTALLATION

- 1. CAST-IN PLATES AND BOLTS ARE EMBEDDED INTO THE CONCRETE SLAB BEFORE THE POUR.
- 2. **NEEDLES** ARE FIXED FIRMLY IN THE SLAB, WITH THE HELP OF CAST-IN BOLTS.
- 3. FACTORY ASSEMBLED SCREEN PANELS, WITH STEEL PURLIN, ARE LIFTED AND FIXED BY THE CRANE. NEEDLES SUPPORT THE SCREEN PANELS.
- 4. PROPS AND WALKWAY BRACKETS ARE FIXED AND THE DECK IS CONSTRUCTED.
- 5. MORE NEEDLES ARE PUT IN THE FOLLOWING POURS UNTIL THE SCREEN GETS TYPICAL.





FIG: TYPICAL SCREEN SECTION

INSTALLATION (Cont.)


THE STAGING SEQUENCE



INSTALLATION (Cont.)



METAL SKIRTING IN WORKING DECK



RUBBER INFILL IN SOLDIER PURLIN



WORKING DECK FROM UNDERSIDE



SCREEN ELEVATION WITH PLATFORMS

4. OPERATION

- ONCE THE SCREEN ASSEMBLY GETS TYPICAL, THERE ARE TWO WAYS TO CLIMB THE SCREENS.
- ♦ CRANE ASSISTED
 - HYDRAULIC JACK ASSISTED

CRANE ASSISTED: THE PROPS ARE DISENGAGED AND CRANE WILL HELP TO LIFT THE SCREENS.

ONCE THE CLIMB IS COMPLETED, THE PROPS WILL BE PLACED BACK AND SCREEN WILL BE SEATED ON UPPER LEVEL NEEDLE.

HYDRAULIC ASSISTED: SINGLE HYDRAULIC RAM WILL BE INSTALLED IN EACH PURLIN, ATTACHED TO THE NEEDLE, AND WILL CLIMB UP TO 3 SCREENS AT ONCE BY THE PUSH OF 10 AMP HYDRAULIC POWERPACK. EACH STROKE WILL CLIMB 2 FT 10 INCHES.



5. COMPLIANCE

OUR SCREEN SYSTEM COMPLIES WITH THE
 AUS/NZ STANDARDS, CONSTRUCTION GUIDES
 AND BEST PRACTICES.

* MOREOVER, WE PROVIDE SITE INSPECTIONS FOR COMPLIANCE CHECKS, ON A PERIODIC BASIS, FOR ENSURING THE SYSTEM IS INSTALLED AND OPERATED COMPLYING WITH THE SYSTEM MANUAL.

WE DEPLOY OUR SITE TECHNICIANS TO
 GUIDE AND HELP IN THE ENTIRE PROCESS
 OF INSTALLATION AND INITIAL OPERATION.




6. SAFETY AND MAINTENANCE

- ♦ FABQUIP IS HIGHLY COMMITTED AND DEDICATED TO SAFETY OF THE WORKERS, SYSTEM AND THE SITE.
- EVERY SINGLE PROCESS IS GUARANTEED
 TO COMPLY WITH THE INDUSTRY BEST
 WORK, HEALTH AND SAFETY STANDARDS.
- WE PROVIDE SAFETY AND MAINTENANCE
 CHECKS QUARTERLY, OR AS REQUIRED, TO
 ENSURE OUR SYSTEM IS SAFE AND WELL
 MAINAINED THROUGHOUT THE
 OPERATION PROCESS.



7. DOCUMENTATION

- ♦ Design (Shop Drawings) Fabquip.
- Safety Screen System Manual Fabquip.
- ♦ Pre and Post Climb Checklist Client.
- ♦ High Risk SWMS Client.



MANUFACTURING




INSTALLATION



TRANSPORTATION





PAST PROJECTS



JF5595-A-S10/B

CRANE ASSISTED SAFETY SCREEN LAYOUT





ANY QUESTIONS???

CONTACT DETAILS

FABQUIP CONSTRUCTION SYSTEMS 36-42 FITZPATRICK ST, REVESBY NSW 2212, AUSTRALIA

PHONE: +61 02 97744099

FAX: +61 02 97742473

EMAIL: info@fabquip.com